


Summary Specification

"The name trusted in roofing since 1906"



APP TORCH

12 – Year Material Warranty Concrete Deck



Deck Requirement
3000 psi Concrete ⁽¹⁾

Insulation
• None

Base Sheet
• None

Cap Sheet
• APP Torch S coated with #401 Premium Fibrated Aluminized Coating 1-1.5 gal / square
• APP Torch G
• APP Torch G FR

Slope Requirement
¼" per foot

Notes:

1. Concrete deck must be primed with #121 Asphalt Primer at a rate of ¼ gal per 100 square feet.
2. Flashings are to be one layer of Cap Sheet installed in accordance with Mule-Hide Standard Details.

PRODUCTS NOT SUPPLIED BY MULE-HIDE PRODUCTS ARE NOT COVERED UNDER THE MULE-HIDE WARRANTY

PLEASE CONSULT THE MULE-HIDE WEBSITE FOR THE MOST CURRENT INFORMATION AT WWW.MULEHIDE.COM