



2-PIECE REGLET

NOTE:
SCREWS THROUGH
COUNTERFLASHING TO
ACT AS TERMINATION
ARE NOT APPROVED



REGLET



NOTES:

1. REFER TO SPECIFICATIONS FOR FLASHING MEMBRANE REQUIREMENTS.
2. LAPS IN FLASHING MUST BE OFFSET FROM LAPS IN FIELD SHEET.
3. CAP SHEET MUST BE HEATED AND GRANULES EMBEDDED IN SURFACE AT ALL LAPS OVER GRANULATED SURFACES WHEN INSTALLING THE CAP SHEET.
4. MAXIMUM FLASHING HEIGHT FOR APP MODIFIED BITUMEN FLASHINGS IS 36". IF WALL IS TALLER THAN 36", SEE DETAIL MHMB-UN-CW06T.
5. ALL VERTICAL SURFACES TO BE PRIMED.
6. IF FLASHING SUBSTRATE IS COMBUSTIBLE, REFER TO DETAIL MHMB-UN-CW11T OR MHMB-UN-CW02T.

**MULE-HIDE
PRODUCTS CO., INC.**

**BASE FLASHING
WITH METAL COUNTERFLASHING
SYSTEMS:**

APP MODIFIED BITUMEN

DETAIL NO.:

MHMB-UN-CW03T

REVISION DATE: MARCH 2015