


NOTES:

1. CUT THE MEMBRANE SO IT EXTENDS A MINIMUM OF 1/2" FROM THE ATTACHMENT POINTS OF THE DRAIN CLAMPING RING.
2. THE CLAMPING RING BOLT MUST PENETRATE THE MEMBRANE.
3. ALL FLASHINGS ON A PVC FLEECEBACK PROJECT MUST BE CONSTRUCTED WITH STANDARD REINFORCED PVC MEMBRANE.
4. APPROXIMATELY 1/8" BEAD OF CUT-EDGE SEALANT IS REQUIRED ON CUT EDGES OF PVC REINFORCED MEMBRANE.
5. THICKNESS OF STANDARD PVC MEMBRANE TO MATCH THICKNESS OF FLEECEBACK PVC MEMBRANE.



**MULE-HIDE
PRODUCTS CO., INC.**

**DRAIN FLASHING
WITH TARGET
SYSTEMS:
MECHANICALLY ATTACHED
PVC FLEECE BACK**

**DETAIL NO.:
MHP-MA-130A**
REVISION DATE: 05/2016